Parkview Exchange Redevelopment

IFC model register

Model file: parkview-exchange.ifc. Schema: IFC4. 6 named objects. Length units are metres. Local vertical datum is 670.000 m; add this to model Z coordinates to obtain the project elevations.

This register is extracted from the IFC object descriptions and property sets. It is a searchable companion to the conceptual model. Project drawings and governing standards remain the design evidence. Geometry includes explicitly identified visualization assumptions and is not a certified survey or a construction model.

Object / IFC class	Register page
FG-ST1 - Finished-grade cover check / IfcBuildingElementProxy	2
BLDG - Building envelope / IfcBuildingElementProxy	3
S1 - Upstream sanitary branch / IfcPipeSegment	4
ST1 - Terminal storm reach / IfcPipeSegment	5
S2 - Sewer service at crossing X1 / IfcPipeSegment	6
W1 - Existing watermain at X1 / IfcPipeSegment	7

Model SHA-256: 9f06f4a31b65c27a4c8bc1e662600e44c850bd30a1d1cd9f42b7c84f367c5a50

Search by object tag, nominal diameter, cover, clearance, lane width, sight distance or pavement layer. Each object page retains its IFC GlobalId and the source drawing or report used for its properties.

Parkview Exchange Redevelopment

IFC object FG-ST1 - Finished-grade cover check

IFC object FG-ST1 is the local finished-grade patch above storm reach ST1 at chainage 0+018. Finished grade is 671.300 m and storm outside crown is 669.650 m. Cover is 1.650 m. Patch extents are illustrative and do not represent a surveyed terrain surface.

IFC class	IfcBuildingElementProxy
GlobalId	2LVQ6sV3XIVfxm6Pa0iRvI
Finished Grade Elevation	671.300 m
Chainage	0+018
Surface Extent	6 m by 2 m local visualization patch only

Source trace

pxr_site-grading-plan_ifr_2026-10-02.pdf · PDF page 2. Model status: Issued for review.

Concept geometry; verify against cited design documents.

Parkview Exchange Redevelopment

IFC object BLDG - Building envelope

IFC object BLDG is a simplified six-storey building envelope with 92 residences and 1,250 m² commercial area. Its model finished floor is 672.250 m, as recorded in C201. Envelope dimensions and 20 m height are illustrative; they are not architectural design commitments.

IFC class	IfcBuildingElementProxy
GlobalId	21GsQxNDDHauOc6RhC7NHe
Finished Floor Elevation	672.250 m
Residential Units	92
Commercial Floor Area	1,250 m²
Storeys	6
Envelope Height	20 m - visualization assumption

Source trace

pxr_client-design-brief_rev0_2026-09-18.pdf · PDF page 1. Model status: Issued for review.

pxr_site-grading-plan_ifr_2026-10-02.pdf · PDF page 1 (related design basis).

Concept geometry; verify against cited design documents.

Parkview Exchange Redevelopment

IFC object S1 - Upstream sanitary branch

IFC object S1 is the upstream sanitary branch. The nominal pipe diameter of IFC object S1 is 200 mm. Its length is 43 m and proposed slope is 0.30%. Peak dry-weather flow is 0.34 L/s for the limited branch only. The model cylinder uses nominal diameter; wall thickness is unresolved.

IFC class	IfcPipeSegment
GlobalId	0NtIT6QF1IJhG5Q8P9XbJS
Nominal Pipe Diameter	200 mm
Length	43 m
Slope	0.30%
Peak Dry Weather Flow	0.34 L/s
Upstream Invert Elevation	668.480 m
Downstream Invert Elevation	668.351 m
Flow Scope	250 m² east retail/frontage only; excludes remaining building service

Source trace

pxr_site-servicing-plan_ifr_2026-10-02.pdf · PDF page 1. Model status: Issued for review.

Concept geometry; verify against cited design documents.

Parkview Exchange Redevelopment

IFC object ST1 - Terminal storm reach

IFC object ST1 is the terminal storm reach. The cover of IFC object ST1 at chainage 0+018 is 1.650 m. Its nominal diameter is 300 mm and slope is 0.25%. No insulation detail is included. The cylinder follows the documented outside crown; nominal diameter is used as a simplified envelope.

IFC class	IfcPipeSegment
GlobalId	1Iqn8UTNHKieVvvXnswxWV
Nominal Pipe Diameter	300 mm
Length	38 m
Slope	0.25%
Cover At Chainage018	1.650 m
Insulation	No insulation detail included
Outside Crown At018	669.650 m

Source trace

pxr_site-servicing-plan_ifr_2026-10-02.pdf · PDF page 2. Model status: Issued for review.

pxr_site-servicing-plan_ifr_2026-10-02.pdf · PDF page 1 (related design basis).

Concept geometry; verify against cited design documents.

Parkview Exchange Redevelopment

IFC object S2 - Sewer service at crossing X1

IFC object S2 is the sewer service at crossing X1. The vertical clearance at IFC crossing X1 is 0.220 m between sewer outside crown 668.380 m and watermain underside 668.600 m. The sewer cylinder diameter is a visualization assumption, not a confirmed design size.

IFC class	IfcPipeSegment
GlobalId	1_G99KApbMVg4kbNz_f1dr
Crossing	X1
Outside Crown Elevation	668.380 m
Vertical Clearance	0.220 m
Envelope Diameter	200 mm - visualization assumption; service sizing not established

Source trace

pxr_site-servicing-plan_ifr_2026-10-02.pdf · PDF page 2. Model status: Issued for review.

Concept geometry; verify against cited design documents.

Parkview Exchange Redevelopment

IFC object W1 - Existing watermain at X1

IFC object W1 is the 150 mm watermain at crossing X1. Its underside elevation is 668.600 m. The sewer service below it has 0.220 m clearance. Utility exposure remains required.

IFC class	IfcPipeSegment
GlobalId	2K$D1jiEzHMQ06k33KWpEl
Nominal Pipe Diameter	150 mm
Underside Elevation	668.600 m
Crossing	X1
Envelope	Nominal diameter, wall thickness unresolved

Source trace

pxr_site-servicing-plan_ifr_2026-10-02.pdf · PDF page 2. Model status: Issued for review.

Concept geometry; verify against cited design documents.