Parkview Exchange Redevelopment

Existing conditions and survey summary

1. Survey control and site

Working site envelope: 84 m east-west by 100 m north-south; area 8,400 m². Local working coordinates are used for this review package. Benchmark BM1 elevation is 671.420 m. Existing site elevations range from 670.85 m to 672.10 m.

Boundary and utility information are preliminary design inputs. Legal boundaries, easements, municipal survey datum and buried plant must be confirmed before detailed design. Utility elevations below are coordination values, not certified as-built records.

2. Existing utility register

MH-S0: existing sanitary maintenance hole, rim 671.220 m, outgoing invert 668.300 m. MH-ST0: existing storm maintenance hole, rim 671.180 m, outgoing invert 668.700 m. Existing municipal watermain is nominally 150 mm.

Crossing X1: watermain underside elevation 668.600 m; proposed S2 sewer-service outside crown elevation 668.380 m. The sewer service passes below the watermain. Utility exposure is required to confirm the assumed outside surfaces.

Project	Issue information
PX-26017	2026-09-22
Parkview Exchange Developments Ltd.	Issued for review
Prepared / checked	JL / AK

Parkview Exchange Redevelopment

Existing conditions and survey summary

3. Constraints and coordination

The east utility corridor constrains excavation and the owner prefers avoiding relocation. The proposed finished floor is 672.250 m. Ground at ST1 chainage 0+018 is proposed to finish at 671.300 m.

No infiltration rate or seasonal groundwater level has been adopted. Field investigation and receiving-system capacity checks are outstanding. These omissions are explicit hold points rather than assumed evidence of acceptable performance.