Parkview Exchange Redevelopment

Servicing design basis and calculations

1. Design basis and limits

This memorandum records the preliminary servicing basis for PX-26017. Applicable editions are EPCOR Volume 3-03, May 2025, together with the current planning, stormwater, approval and water publications associated with the project. Approval of an alternate detail is not assumed.

The network is divided into S1, a limited upstream branch serving 250 m² east retail/frontage, and S2, the remaining building service. A complete accepted whole-development flow model and downstream capacity review are not yet available.

2. Sanitary branch S1

Peak dry-weather flow assigned to upstream branch S1 is 0.34 L/s. This is not the total flow from 92 residences. The allocation is provisional and must be reconciled with the accepted neighbourhood design report.

The proposed pipe diameter for sanitary branch S1 is 200 mm PVC. Selected S1 geometry: 200 mm PVC; length 43.0 m; upstream invert 668.480 m; downstream invert 668.351 m. Fall = 43.0 × 0.0030 = 0.129 m. Grade = 0.129 / 43.0 × 100 = 0.30%. The shallow grade was selected to reduce excavation; compliance with the upstream criterion is unresolved.

Project	Issue information
PX-26017	2026-10-03
Parkview Exchange Developments Ltd.	Issued for review
Prepared / checked	JL / AK

Parkview Exchange Redevelopment

Servicing design basis and calculations

3. Storm reach ST1

ST1 is a 300 mm terminal storm reach, 38.0 m long at 0.25% grade. Outside crown levels are 669.695 m at 0+000, 669.650 m at 0+018 and 669.600 m at 0+038. Total fall = 38.0 × 0.0025 = 0.095 m.

Cover at 0+018 = finished grade 671.300 minus outside crown 669.650 = 1.650 m. No insulation design or accepted alternate cover detail is provided. Upstream minimum slope and shallow-cover provisions require separate review.

4. Utility crossing and hold points

X1 is the S2 sanitary sewer service crossing below the 150 mm watermain. Vertical clearance = 668.600 - 668.380 = 0.220 m. Dimensions are outside-to-outside and require field confirmation.

Before release: revise or resolve S1 and ST1 slopes; provide adequate insulation if retaining shallow ST1 cover; coordinate X1 clearance; complete whole-site flows, hydraulic network analysis and receiving-system acceptance. No pipe capacity, fire-flow sufficiency or infiltration performance conclusion is issued here.