North Ridge Highway Intersection Upgrade

Traffic count worksheet and dataset provenance

1. Count scope and provenance

Authored example dataset for NRH-26104, north industrial access at approximate project chainage 0+300. The following PM peak-hour observations are simulated training values; no traffic survey was conducted. Dry-weather weekday conditions are a scenario assumption.

The 900 vehicles/hour intersection demand is a one-hour movement total, not AADT. The separately adopted 2026 AADT of 7,800 vehicles/day and 14% heavy vehicles are planning inputs carried from NRH-TIA-001; annualization factors and a classified survey are not available.

Project	Issue information
NRH-26104	2026-09-10
North Ridge Industrial Lands Partnership	Issued for review
Prepared / checked	JL / AK

North Ridge Highway Intersection Upgrade

Traffic count worksheet and dataset provenance

2. PM peak turning movements — base 2026

Approach	Movement	Vehicles/hour
Eastbound	Through	390
Eastbound	Left to north access	30
Westbound	Through	365
Westbound	Right to north access	25
North access	Left to eastbound	50
North access	Right to westbound	40
All approaches	Total entering intersection	900

Approach totals are eastbound 420, westbound 390 and north access 90 vehicles/hour. Each vehicle is counted once at its entering approach; do not add departures to the entering total.

North Ridge Highway Intersection Upgrade

Traffic count worksheet and dataset provenance

3. Development increment and distribution

Trip direction	Assignment	Added vehicles/hour
Entering development	From eastbound approach	35
Entering development	From westbound approach	25
Exiting development	North access left	25
Exiting development	North access right	15
Total increment	60 entering + 40 exiting	100

The development increment is a separate scenario from background growth. Do not apply the 14% daily heavy-vehicle share to individual turning movements without classified peak-hour observations.

North Ridge Highway Intersection Upgrade

Traffic count worksheet and dataset provenance

4. Count QA and study limits

Movement sum: 390 + 30 + 365 + 25 + 50 + 40 = 900 vehicles/hour. Development allocation sum: 35 + 25 + 25 + 15 = 100 vehicles/hour. These arithmetic checks establish internal consistency only.

Outstanding: count dates and intervals, raw tally sheets, vehicle classification, seasonal/weekly factors, pedestrian and cycle counts, queue observations and authority acceptance. No saturation flow, capacity, level of service or turn-lane storage result can be inferred from this worksheet alone.