Parkview Exchange Redevelopment

Utility verification and level reconciliation

1. Verification basis and limitations

This fictional training record reconciles the PX-26017 survey summary, C102 profile and PX-DM-001. No site investigation was performed. Elevations use the project local working datum; BM1 = 671.420 m. The figures below are design-record values, not exposed-utility observations.

The verification sequence is utility-owner records, locating, permitted exposure, surveyed outside surfaces, then revised design. A locating mark establishes plan position only and cannot certify cover or vertical separation.

Project	Issue information
PX-26017	2026-10-06
Parkview Exchange Developments Ltd.	Issued for review
Prepared / checked	JL / AK

Parkview Exchange Redevelopment

Utility verification and level reconciliation

2. Register of design-record levels

Asset / station	Design-record level	Source / verification status
BM1	671.420 m	PX-SV-001; datum connection pending
ST1 / 0+018 ground	671.300 m	C201 proposed finished grade
ST1 / 0+018 crown	669.650 m	C102 proposed outside crown
X1 water underside	668.600 m	PX-SV-001 coordination assumption
X1 S2 sewer crown	668.380 m	C102 proposed outside crown

No measured outside pipe diameter, bedding thickness or utility-owner tolerance has been adopted. Do not substitute an invert elevation for an outside crown.

Parkview Exchange Redevelopment

Utility verification and level reconciliation

3. Vertical reconciliation

ST1 cover at station 0+018 is 671.300 - 669.650 = 1.650 m, measured from proposed finished grade to outside crown. The 300 mm nominal diameter is not an additional deduction from that cover.

X1 outside-surface clearance is 668.600 - 668.380 = 0.220 m. Against a 0.300 m coordination target, the numerical difference is 0.080 m. This target is a design-review input; the associated EPCOR source establishes the applicable crossing requirement.

Parkview Exchange Redevelopment

Utility verification and level reconciliation

4. Verification work order

Item	Required evidence	Release owner
UV-01 / X1	Expose watermain; survey underside and horizontal position	Utilities coordinator
UV-02 / ST1	Confirm finished-grade tie-in and outside crown	Civil designer
UV-03 / S1 outlet	Confirm MH-S0 connection invert and benching	Survey / utility owner
UV-04 / whole site	Accepted S1/S2 flow allocation and downstream review	Civil lead

Hold point: do not release revised crossing or insulation details until the relevant elevations and receiving-system interfaces are confirmed. No utility exposure ticket or acceptance certificate is attached.