Willow Creek Bridge Renewal

Owner brief and adopted design basis

CLIENT / OWNER	Prairie County Transportation (fictional)
DOCUMENT / REVISION	WC-CR-001 / P01 - preliminary
LOCATION / STATUS	Rural Alberta - fictional site / demonstration concept

Project scope

Replace a deteriorated rural crossing with a 24 m single-span steel-girder bridge and concrete deck. The proposed carriageway is 8.0 m wide within an 8.4 m deck. Prairie County Transportation and this site are fictional demonstration entities.

Adopted references

For this demonstration contract, adopt Alberta Transportation Bridge Structures Design Criteria, Version 9.0, January 2022, including Section 4.2 for bridge deck geometry. The reference is a contract design basis; this brief does not establish the latest publication or statutory applicability.

Approach constraints

Minimize approach raising near adjacent farm accesses. The owner requests evaluation of a 0.35% longitudinal deck grade. Any departure requiring approval must be documented before design release.

Release requirements

Confirm deck drainage crossfall, longitudinal grade and any required approval. Complete hydraulic and geotechnical design before advancing the foundation or freeboard decisions. No construction release is authorized.