Mill Creek Corner Infill

Client requirements and design brief

CLIENT / OWNER	Rivermark Developments
DOCUMENT / REVISION	MC-CR-001 / P01 - preliminary
LOCATION / STATUS	Bonnie Doon, Edmonton / concept review

Project scope

Four side-by-side infill homes on a 20 m by 54 m corner parcel. Concept review only; this is not an issued-for-construction package.

Architectural interface

The current landscape allocation limits the overall width of each box planter to 400 mm. The allocation may be revised following engineering review. Maintain a continuous accessible entrance route.

Drainage objectives

Provide two box planters for roof runoff from a combined 320 m² roof catchment. Confirm the applicable Corner Lot Infill LID Guidelines and obtain an accepted drainage connection arrangement before design release. A planter is not assumed to waive private storm-servicing requirements.

Review hold points

Confirm planter width, underdrain discharge route, overflow routing and groundwater separation. No construction authorization is implied by this brief.