Mill Creek Corner Infill

Site constraints and preliminary drainage checks

CLIENT / OWNER	Rivermark Developments
DOCUMENT / REVISION	MC-TN-002 / P01 - preliminary
LOCATION / STATUS	Bonnie Doon, Edmonton / concept review

Catchment accounting

Parcel area: 1,080 m². Combined roof catchment directed to P1/P2: 320 m². Other paved and landscaped areas are outside this preliminary planter check. Two 20 m by 0.4 m overall planter footprints total 16 m²; this is not a verified effective media area or treatment-volume calculation.

Existing services

The concept utility sketch identifies a combined sewer at C1. No accepted storm-only underdrain connection is currently established. Utility locations and invert levels require survey and confirmation with EPCOR.

Ground conditions

The assumed seasonal groundwater level is 2.8 m below grade. No project borehole or infiltration test has been completed. Confirm field conditions before relying on the planter section or selecting the discharge arrangement.

Required coordination

Resolve the architectural width allocation and underdrain outlet before detailed design. The preliminary note does not establish capacity, infiltration performance or approval of the overall drainage design.