North Ridge Highway Intersection Upgrade

Traffic impact assessment

1. Study basis and scope

The 2026 base-year traffic dataset is AADT 7,800 vehicles/day and 14% heavy vehicles. Adopt 2.0% annual non-compounded background growth for the preliminary traffic assessment. Opening year is 2027.

The current assessment includes 2027 opening and 2037 ten-year combined-traffic horizons only. No 2047 twenty-year combined-traffic analysis is included. This omission is a study hold point, not an assertion that the shorter horizon is sufficient.

2. Forecast calculations

Background AADT in year y = 7,800 × [1 + 0.02 × (y - 2026)]. Opening 2027 background = 7,956 vehicles/day. 2037 background = 9,516 vehicles/day. These daily values exclude the new development increment.

Base 2026 peak approach flows are eastbound 420, westbound 390 and north access 90 vehicles/hour. New development adds 100 peak-hour trips: 60 entering and 40 exiting. Entries assign 35 eastbound and 25 westbound; exits assign 25 left and 15 right.

Project	Issue information
NRH-26104	2026-09-15
North Ridge Industrial Lands Partnership	Issued for review
Prepared / checked	JL / AK

North Ridge Highway Intersection Upgrade

Traffic impact assessment

3. Combined peak-hour screening

2027 combined approach flows: eastbound 463, westbound 423, north access 132 vehicles/hour; total 1,018. 2037 combined approach flows: eastbound 547, westbound 501, north access 150; total 1,198. Values are rounded after applying the stated linear background growth.

These are demand screens only. No calibrated capacity model, HCM level-of-service result or validated queue/storage length is supplied. Complete the 2047 combined demand and accepted capacity/safety analysis before final geometry.

4. Traffic-to-pavement interface

Base-year heavy traffic = 7,800 × 0.14 = 1,092 vehicles/day, two-way. This is a heavy-vehicle count, not an equivalent standard axle load. Reconcile vehicle classification and axle-load inputs with the pavement discipline.

The pavement draft uses a different base-year AADT and truck share. Confirm the common count source, count year, site increment and forecasting method before either discipline freezes its design basis.